No.	Quantity.	Description	Unit	Rates In Figures	Rates In Words
8	53.93	Providing and laying in position **reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal**, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc. including cost of all materials, labour, HOM of machinery, curing, complete as per specifications	Cum	6491.88	Rupees Six Thousand Four Hundred Ninety One and Eighty Eight Paise Only
9	6.20	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications Specification No. KBS 4.6.3 **TMT Bars FE 500**	Tonne	60534.00	Rupees Sixty Thousand Five Hundred Thirty Four Only
10	270.58	Providing and removing centering, shuttering, strutting, propping etc., and **removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm** including cost of all materials, labour complete as per specifications	Sqm	331.78	Rupees Three Hundred Thirty One and Seventy Eight Paise Only
11	111.71	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications	Sqm	979.56	Rupees Nine Hundred Seventy Nine and Fifty Six Paise Only
12	102.20	Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs (c) After two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 300x300mm square (e) The whole	Sqm	976.32	Rupees Nine Hundred Seventy Six and Thirty Two Paise Only
13	84.42	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to **ceiling** including rounding off corners wherever required smooth rendering. Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	Sqm	208.44	Rupees Two Hundred Eight and Forty Four Paise Only

	Quantity.	Description	Unit	Rates In Figures	Rates In Words
14	198.06	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering. Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	238.68	Rupees Two Hundred Thirty Eight and Sixty Eight Paise Only
15	282.48	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications	Sqm	27.00	Rupees Twenty Seven Only
16	6.86	Providing wall black boards in CM 1:3 with two coats of black paint including finishing etc., complete	Sqm	992.52	Rupees Nine Hundred Ninety Two
17	115.64	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering. Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	Sqm	213.84	Rupees Two Hundred Thirteen and Eighty Four Paise Only
18	7.56	Supplying and fixing pressed steel door frames size 125x65 mm manufactured from 1.25mm thick carbon steel or imported steel strips with mitred joints of 900 for door openings and shutters made out of seasoned Honne wood, styles of 30 mm thick with lock rail of 160 mm width, top and side rails of 100 mm width and bottom rails of 250 mm width and panel filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be rot proof vermin proof, heat resistant guaranteed against shrinkage warpage and such other defects for a period of 3 years. This shall be as per approved drawings, specification and direction including cost of conveyance, manufacturing, painting with enamel paint 2 coats over primer coat, cost of labour for all items of work, machinery, equipment and all other incidental charges with all lead, lift, loading and unloading etc., complete. The Hollow portion of the frame to be filled with cement concrete 1:2:4	Sqm	3780.00	Rupees Three Thousand Seven Hundred Eighty Only
19	10.50	"Supplying and fixing pressed steel window frame of size 100 x 50mm manufactured from 1.25 mm thick carbon steel or imported steel strips with neat mitred joints at 900degree for window openings and shall be suitable to fix M.S. grills as per design and drawings using 12mm dia rods at 100mm Centre to Centre horizontally and two members of M.S. flats of 6mmx40mm size at 150mm apart, welded into a frame of 6mmx40mm size M.S. flats with 16mm size lugs, and 8 Nos. of 100mm size hinges, 4 Nos of Butt Stay pins and 4 Nos. Tower bolts and shutters half panelled and hallf glazed with shutters made out of seasoned honne wood, styles of 30mm thick and 100mm width and rails of 30mm thick and 100mm width and using 4mm thick pin headed glass and panel, filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be rot proof vermin proof, heat resistant guaranteed against shrinkage, warp age and such other defects for a period of 3 years.This shall be as per approved drawing, specification and direction including cost of conveyance, manufacturing painting with 2 coats enamel paint over one coat of primer, cost of labour for	Sqm	4104.00	Rupees Four Thousand One Hundred Four Only
20	172.86	Flooring with 25mm to 40mm thick polished **tandur blue stone slabs** using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications	Sqm	1210.68	Rupees One Thousand Two Hundred Ten and Sixty Eight Paise Only

o.	Quantity.	Description	Unit	Rates In Figures	Rates In Words
21	405.24	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications.	Sqm	76.68	Rupees Seventy Six and Sixty Eight Paise Only
22	254.00	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials labour, complete as per specifications with primer	Sqm	90.72	Rupees Ninety and Seventy Two Paise Only
23	12.00	Providing and fixing on wall surface 4.0 kg / sq.cm H.D.P.E. rain down water pipes 90 mm outer dia approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps wall plugs, screws including cost of materials, labour, complete as per specifications	m	462.24	Rupees Four Hundred Sixty Two and Twenty Four Paise Only
24	65.00	Providing and laying to required line and slope roofing with corrugated asbestos cement sheet 6mm thick fixed with galvanised iron J or L hooks, bolts and nuts 8mm dia C.I. plain and bitumen washers over the existing purlins, rafters and trusses including cost of materials, labour, complete as per specifications.	Sqm	390.96	Rupees Three Hundred Ninety and Ninety Six Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

20/09

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer. ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of the work:- Construction of additional class rooms to Govt. Higher primary school of Singapura in Ward No. 11

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	84.73	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, **in ordinary soil** not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m after breaking of clods complete as per specifications	Cum	204.12	Rupees Two Hundred Four and Twelve Paise Only
2	23.47	Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, **in foundation** including cost of all materials, labour, HOM of machinery curing complete as per specifications	Cum	5256.36	Rupees Five Thousand Two Hundred Fifty Six and Thirty Six Paise Only
3	47.14	Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6, stone** hammerd dressed in courses not less than 20 cms high, bond stones at two m apart in each course including cost of materials, labour, curing complete as per specifications	Cum	4521.96	Rupees Four Thousand Five Hundred Twenty One and Ninety Six Paise Only
4	12.19	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m apart in each course including cost of materials, labour, curing complete as per specifications	Cum	5405.40	Rupees Five Thousand Four Hundred Five and Forty Paise Only
5	27.99	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications	Sqm	105.84	Rupees One Hundred Five and Eighty Four Paise Only
6	84.73	**Refilling available earth** around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications	Cum	82.08	Rupees Eighty Two and Eight Paise Only
7	220.86	Providing and removing **centering, shuttering, strutting, propping** etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons	Sqm	249.48	Rupees Two Hundred Forty Nine and Forty Eight Paise Only